



# Design and Construction of the 100 - metre Span UHPC Batu 6 Segmental Box Girder Bridge

Prepared By: Adj. Assoc. Prof Ir. Dr VOO Yen Lei

10<sup>th</sup> March 2016

**DURA**<sup>®</sup>  
like concrete • like steel



**UNSW**



## Bio-data

- i. Founder / CEO / Executive Director of Dura Technology
- ii. PhD in Civil Engineering – University New South Wales, Sydney, Australia, 2004
- iii. 15 over years experience in the development of UHPC Technology (bridge engineering)
- iv. Adjunct Associate Professor of University of New South Wales (Australia)
- v. More than 70 publications (including a Book)
- vi. 2 times Malaysia Book of Records holders
- vii. Prestigious Entrepreneurs Award Winner 2015
- viii. Prestigious Company Award Winner 2015
- ix. Member of FIB Task Group 6.5



# **UHPC Bridges in Malaysia**

## **(OVERVIEW)**

# Where is Malaysia??

---



A small and young country, with population and GDP of 9.6% and 4.6% respectively of USA.



# Where is DURA Bridges Have Been Used in Malaysia?

## Kedah

On-going bridges = 13 nos.

## Perak

Completed and on-going bridges = > 51 nos.

## Selangor

Completed and on-going bridges = 4 nos.

## Kelantan


Completed and on-going bridges = 10 nos.

## Pahang


Completed and on-going bridges = 15 nos.


## Negeri Sembilan


Completed and on-going bridges = 4 nos.



# Where is UHPC Bridges Have Been Used in Malaysia?









# Kampung Linsum Bridge (50m) (Negeri Sembilan, 2010)

1


## 1. 50m Kampung Linsum Bridge, NS (2011)





(Year 2011)

2. 25m Sungai Itik Bridge, Gopeng, PRK



(3) 18m Ulu Kampar Bridge, Gopeng, PRK (2012)





# Year 2012

(4) 78m Wesport Access Bridge 25,  
Port Klang, SLG (2012)



(6) 12m Kg. Beng Bridge,  
Lenggong, PRK (2012)



(5) 32m Ulu Kinta Bridge,  
Ipoh, PRK (2012)



(7) 30m Ulu Chemor Bridge, Chemor, PRK (2012)



# 40m Sk. Taayah Footbridge (2012)

8

(8) 40m Sekolah Taayah Footbridge, Ipoh, PRK (2012)






## (Year 2013)





# (Year 2013)





## (Year 2013)





# (Year 2013)

(21) 50m Sungai Kurau Bridge 1, PRK (2013)

21



(22) Sungai Kurau Bridge 2, PRK (2013)

22





# (Year 2014)

(23) Tapak Rapi Bridge, PRK (2014)



23



24

(24) MINES Shopping Centre Bridge, SLG (2014)

(25) Wisma LKIM Bridge, SLG (2014)



25



26



# (Year 2014)





# (Year 2014)



(33) 58m Kampung Merdeka Bridge, PRK (2015)



(34) 200m CFS Bridge, PRK (2014)





# (Year 2014)






# (Year 2015)

(39) 50m Sungai Ijok Bridge, PRK (2015)



(40) 25m Kok Lanas Bridge 1, KLT (2015)



(41) 40m Kok Lanas Bridge 2, KLT (2015)





(Year 2015)





(Year 2015)









# Membina Jalan dan Jambatan di Kawasan Kampung Batu 6, Bandariang, Gerik, Daerah Hulu Perak, Perak D.R. (2014)

## 100m Single Span Bridge



# Bridge Location









# Design Load


---

- The traffic loading used was according to the specification of the bridge design code BD37/01 [5].
- At SLS stage, using HA-UDL (25.2kN/m UDL) and KEL (120kN point load) and pedestrian loadings (5kPa x 1m width = 5kN/m).
- At ULS, both of the HA+KEL and 30 units HB loadings (i.e. 4 axles x 300 kN/axle) combined with pedestrian loadings (whichever governed).
- 30unit HB loading: 30t x 4 axles = 120 ton (nominal); 120t x 1.1 = 132 ton (SLS); 120t x 1.3 = 156 ton (ULS)




|                                                        | SLS                    |                            |                                                            |                                                        | ULS                                            |                                             |
|--------------------------------------------------------|------------------------|----------------------------|------------------------------------------------------------|--------------------------------------------------------|------------------------------------------------|---------------------------------------------|
| (1)                                                    | (2)<br>Moment<br>(kNm) | (3)<br>Shear<br>Force (kN) | (4)<br>Deflection <sup>3</sup><br>Theo. (mm)               | (5)<br>Deflection<br>Field (mm)                        | (6)<br>Moment<br>(kNm)                         | (7)<br>Shear<br>Force (kN)                  |
| SW of box-girder<br>( $G_1 = 70$ kN/m)                 | 87,500                 | 3,500                      | -49.6 (net)<br>(1st Stg PT)<br>-81.4 (net)<br>(2nd Stg PT) | -50 (net)<br>(1st Stg PT)<br>-78 (net)<br>(2nd Stg PT) | <b>100,625</b><br><b>(60%)</b>                 | <b>4,025</b><br><b>(60%)</b>                |
| SW of G.I. railing<br>( $G_2 = 3$ kN/m)                | 3,750                  | 150                        | + 13.6<br>(incremental)<br>= -67.8 (net)                   | + 36<br>(incremental)                                  | <b>4,312.5</b>                                 | <b>172.5</b>                                |
| SW of premix ( $G_3 = 5.175$ kN/m)                     | 7,762.5                | 310.5                      | + 28.2<br>(incremental)<br>= -39.6 (net)                   | = -42 (net)                                            | <b>11,320</b>                                  | <b>453</b>                                  |
| Live load 1 ( $Q_1 = 25.1$ kN/m<br>equivalent HA)      | 37,672                 | 1,509                      | + 136.8<br>(incremental)<br>= +97.2 (net)                  | No Data                                                | <b>47,090</b><br><b>(27.8%)</b>                | <b>1,886</b><br><b>(27.8%)</b>              |
| Live load 2 ( $Q_2 = 300$ kN x 4 axles,<br>30 unit HB) | N/A                    | N/A                        | N/A                                                        | N/A                                                    | <b>37,128</b>                                  | <b>1,425</b>                                |
| Live load 3 ( $Q_3 = 3.07$ kN/m<br>pedestrian)         | 3,837.5                | 153                        | + 14<br>(incremental)<br>= +111.2 (net)                    | No Data                                                | <b>5,756</b>                                   | <b>230</b>                                  |
| Total                                                  | 140,522                | 5,623                      |                                                            |                                                        | <b><math>M_{Ed} =</math></b><br><b>169,104</b> | <b><math>V_{Ed} =</math></b><br><b>6767</b> |

# SLS Stresses (Top Extreme Fiber)





# SLS Stresses (Bot Extreme Fiber)





## ULS – Flexural Capacity

---

- $M_{Ed}^+ = 169,103\text{kNm}$  (@ S.S. scenario)
- Using Material Factor:
  - UHPC = 1.3 (JSCE No.9, 2006)
  - Tendon = 1.15 (EC2)
- $M_{Rd}^+ = 215,229\text{kNm} >> M_{Ed}^+ = 169,103\text{kNm}$   
(OK!!!)
- Flexure Capacity is adequate!!!!





# ULS – Shear Capacity (None Joint Section) (JSCE No.9, 2006)

---

- $V_{Ed} = 6,764 \text{ kN}$  (Av. Web Shear Stress = 5.64 MPa)
- Using Material Factor:
  - UHPC  $\phi_c = 1.3$  (JSCE No.9, 2006)
  - Tendon  $\phi_p = 1.15$  (EC2)
- Using Member Reduction Factor
  - $\phi_b = 1.3$
- $V_{Rd} = 10,107 \text{ kN} \gg V_{Ed} = 6,764 \text{ kN}$  (OK!!!)
- Shear Capacity at none joint section is adequate!!!!



# ULS – Shear Capacity (@ Joint Section) (Voo et al., 2015)

---

- Ref: **Voo, Y.L.**, Foster, S.J., and Voo, C.C., (2015).  
”Ultrahigh-Performance Concrete Segmental Bridge Technology: Toward Sustainable Bridge Construction.”  
*Journal of Bridge Engineering*, Vol. 20, No.8, August, SPECIAL ISSUE: Design, Analysis, and Construction of Segmental Bridges, B5014001. ASCE.
- $V_{Ed} = 6,764 \text{ kN}$
- Using Member Reduction Factor  $\phi = 0.7$
- $V_{j,Rd} = 19,224 \text{ kN} \gg V_{Ed} = 6,764 \text{ kN}$  (OK!!!)
- Shear Capacity at joint section is adequate!!!!




# Mechanical Property of DURA

| Properties                                                        | Unit | Min  | Max  | Mean              | S.D.             | Characteristic |
|-------------------------------------------------------------------|------|------|------|-------------------|------------------|----------------|
| <b>1 Day Cube Compressive Strength, <math>f_{cu,1d}</math></b>    | MPa  | 82   | 95   | 85 <sup>1</sup>   | 4.4 <sup>1</sup> | 78             |
| <b>28 Days Cube Compressive Strength, <math>f_{cu,28d}</math></b> | MPa  | 165  | 185  | 173 <sup>1</sup>  | 6.2 <sup>1</sup> | 163            |
| <b>Flexural Strength, <math>f_{cf,28d}</math></b>                 | MPa  | 26.6 | 31.2 | 29.1 <sup>2</sup> | 2.8 <sup>2</sup> | 24.4           |
| <b>Modulus of Elasticity, <math>E_o</math></b>                    | GPa  | 44.8 | 46.8 | 45.6 <sup>3</sup> | N/A              | N/A            |
| <b>Poisson's Ratio, <math>\nu</math></b>                          |      | 0.19 | 0.21 | 0.2 <sup>3</sup>  | N/A              | N/A            |

There are a total of 80 pours in the manufacturing of one single girder. A total of min. 480 cubes and 240 prisms quality control samples were made and tested destructively to produce the above results.

Note: 1. Out of min 240 cube samples; 2. Out of 240 prism samples; 3. Out of 3 cylinder samples

# Matched Casting





# Transportation of Segments

---




# Unload Segments at Site using 45t crane

---






# Temporary Supports



# Assembly Method





# LAUNCHING METHOD





# Assembly Temporary Steel Truss

---



**DURA**



550t crawler crane is used mainly  
to assembled the last steel frame

---





# Assembly Segment Using Trolley





# Assembly of 4<sup>th</sup> Segment



# Inside the Box

---





# Assembling the Last Segment

---



# Fully Assembled in 10 days

---





# Post Tensioning Work





# Completed After 1 Year

---





# Completed After 1 Year

---



**DURA**®



## Advantageous

- No column in river
- Beam light-weight
- Shorter construction time
- Easier to construct / less environmental disturbance
- More durable
- More economical
- Maintenance free